

भारत सरकार Government of India
रेल मंत्रालय Ministry of Railways
रेलवे बोर्ड Railway Board

(E-File No.- 3383703)
New Delhi, Date: 13.09.2024

No. 2022/M(C)/141/6Safety

General Managers
All Zonal Railways

Sub: Pit line infrastructure in Coaching Depots

During the latest safety review meeting, Zonal Railways had been advised to review the status of pit line infrastructure and progress of new works for maintenance of coaching stock. It has been decided to review the same with each Zonal Railway in the coming week.

The details regarding the pitlines as per the format attached at annexure may be shared with Board by 16.09.2024 in this regard. A pit line chart may also be made out and shared with the data.

The consolidated reply from each Zone may please be mailed on (somech538@gmail.com).

For necessary action please.

DA: Annexure.



13/09/24

(प्रांजल मिश्रा)
संयुक्त निदेशक / यांत्रिक इंजी. कोचिंग-II
रेलवे बोर्ड

C/- PCMEs/All Zonal Railways- For kind information and necessary action please.

Annexure

Zone	
Depot	
No. of Pitlines in Depot	

Details of each Pitline				
		Pitline 1	Pitline 2	Pitline 3...
Status of Pit Line (Available /Commissioned ,Sanctioned/Under Construction/Under Commissioning , Under Planning				
If Available /Commissioned, Whether As per CAMTECH design	Yes/No			
Coach Capacity	In terms of LHB Coaches			
Length of pit line	Length in meter			
Depth of pit line as per CAMTECH standard or higher	Yes/NO			
Availability of Illumination in Pit	Yes/NO			
Availability of Illumination Below Catwalk	Yes/NO			
Availability of Illumination above Catwalk (Over Head light)	Yes/NO			
Provision of OHE/Top wire	Yes/No			
Provision of electric connection for Battery Charging	Yes/NO			
Availability of Welding points	Yes/No			
RMPU testing without Power Car	Yes/No			
Availability of Electric connection for mechanized cleaning machine (at least one connection for every 3 coaches)	Yes/No			
Provision of watering facility (pipeline)	Yes/No			
Provision for Power car Fueling	Yes/No			
Availability of permanent ladder with interlock for VB roof	Yes/No			
Whether adequate drainage provided to prevent water logging	Yes/No			
Adequate compressor capacity with pneumatic piping	Yes/No			
Provision of Catwalk	Yes/No			
Cat Walk Condition (Ok, Not ok (required Minor/Major repair)	Yes/No			
Provision of Covered Shed	Yes/No			